

TOWN OF PRESQUE ISLE, VILAS COUNTY, WISCONSIN

BID SPECIFICATION: Excavation and straightening a portion of Viola Ln from 11632 to 11664 including excavation of two hills and filling in low area between the two hills.

1. Realign road to straighten out the downhill approach from both the west and the east.
2. Begin excavation work 100 feet east of fire address 11632.
3. Remove 6 feet from the highest point of the eastern hill and place cut dirt in the low area, sloping back side slopes as needed.
4. Remove 8 feet from the highest point of the western hill and place cut dirt in the low area, sloping back side slopes as needed.
5. Clear and grub as needed.
6. Lay 1200 feet of new gravel 8 inches thick and 24 feet wide (where possible).
7. Remove existing culvert in this area and install a new culvert of appropriate size (diameter & length) in the new road bed area.
8. Salvage topsoil on slopes, seed, and emat.
9. Construct existing driveways to meet the new road bed.
10. Keep road passable to local traffic during construction activity.

The Town of Presque Isle reserves the right to reject any or all proposals or to accept the proposal deemed most advantageous to the town.